

AD-A072 227

O'BRIEN AND GERE ENGINEERS INC PHILADELPHIA PA JUSTIN--ETC F/G 13/2
NATIONAL DAM INSPECTION PROGRAM. KINTZ CREEK DAM, NDI-PA-00415,--ETC(U)
MAY 79


DACW31-79-C-0010

NL


UNCLASSIFIED

| OF |

AD
A072 227



END
DATE
FILMED
9-79
DDC



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

DELAWARE RIVER BASIN
KINTZ CREEK, PIKE COUNTY

(1)

PENNSYLVANIA


ORIGINAL CONTAINS COLOR PLATES: ALL DDC
REPRODUCTIONS WILL BE IN BLACK AND WHITE

KINTZ CREEK DAM

NDI - PA 00415
PA DER 52-159
SCS PA-439

LEVEL

PHASE I INSPECTION REPORT NATIONAL DAM INSPECTION PROGRAM



Distribution Unlimited
Approved for Public Release
Contract No. DACW31-79-C-0010



Prepared By

O'BRIEN & GERE

Justin & Courtney Division
PHILADELPHIA, PENNSYLVANIA
19103

DDC
RECEIVED
AUG 6 1979
A

FOR
DEPARTMENT OF THE ARMY
BALTIMORE DISTRICT CORPS OF ENGINEERS
BALTIMORE, MARYLAND
21203

MAY 1979

79 08 06 06 8

DA072227

DDC FILE COPY

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DDC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

DELAWARE RIVER BASIN

Name of Dam: Kintz Creek Dam

County and State: Pike County, Pennsylvania

Inventory Number: PA 00415

PHASE I INSPECTION REPORT

⑥ NATIONAL DAM INSPECTION PROGRAM

National Dam Inspection Program. Kintz Creek Dam, NDI-PA-00415, PA-DER-52-159, SCS-PA-439, Delaware River Basin, Kintz Creek, Pike County, Pennsylvania. Phase I Inspection Report.

⑪ May 79

Prepared by:

O'BRIEN & GERE ENGINEERS, INC.
JUSTIN & COURTNEY DIVISION

⑫ 72 p.

⑮ DACW31-79-C-0010

For:

DEPARTMENT OF THE ARMY
Baltimore District, Corps of Engineers
Baltimore, Maryland 21203

ORIGINAL CONTAINS COLOR PLATES: ALL DDC
REPRODUCTIONS WILL BE IN BLACK AND WHITE

✓ 410 760

79 08 06 06 8

SP

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected, and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession For	
NTIS GAMA1	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or special
A	Feb

PHASE I REPORT
NATIONAL DAM INSPECTION PROGRAM

Name of Dam: Kintz Creek Dam ID # PA 00415
State Located: Pennsylvania
County Located: Pike
Stream: Kintz Creek
Coordinates: Latitude 41° 16.9' Longitude 75° 14.0'
Date of Inspection: December 5, 1978

ASSESSMENT

Kintz Creek Dam is a zoned compacted earth embankment approximately 1,180 feet long and 36 feet high at its maximum section. The dam has a two stage, drop inlet, closed conduit spillway (Principal Spillway), and a grass covered spillway (Emergency Spillway) which is located at the left (looking downstream) abutment. The primary purpose of the structure is flood control.

Examination of the results of the hydrologic and hydraulic analyses indicates that the spillway system is capable of passing approximately 58 percent of the Probable Maximum Flood (PMF) without the dam being overtopped. The Spillway Design Flood (SDF) for this "High" hazard structure is the PMF. Therefore, the capacity of the spillway system is classified as "Inadequate".

Based on visual observations and review of the information obtained from the Pennsylvania Department of Environmental Resources, Kintz Creek Dam appears to be in fair condition. However, certain items require further investigation:

1. Engage a professional engineer experienced in the design and construction of dams to analyze the Zone V material and perform stability analyses. If warranted, specific corrective action should be identified and taken.
2. Low areas along the top of the dam, that appear to be the result of maintenance traffic or poor grading, should be restored to the design top of dam elevation as required.
3. The downstream area near the Emergency Spillway outlet channel and the area along the downstream toe of the earth embankment should be regraded to prevent ponding of water.

4. A maintenance program, independent of the yearly inspection reports, should be developed and implemented. This program should include cutting the grass on a regular basis to enhance visual inspection of the embankment.
5. A warning system should be developed. During periods of heavy rainfall, the dam should be monitored and downstream residents alerted in the event of an impending failure.

O'BRIEN & GERE ENGINEERS, INC.
JUSTIN & COURTNEY DIVISION

Will M. Heiser

Will M. Heiser, P.E.
Vice-President
Pennsylvania Registration #006926



Date: JUNE 8, 1979

James W. Peck
Approved By

JAMES W. PECK
Colonel, Corps of Engineers
District Engineer

Date: 16 JUL 1979



OVERVIEW
KINTZ CREEK DAM
PIKE COUNTY, PENNSYLVANIA

TABLE OF CONTENTS

	<u>PAGE</u>
SECTION 1 - PROJECT INFORMATION	
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	3
SECTION 2 - ENGINEERING DATA	
2.1 Design	6
2.2 Construction	6
2.3 Operation	6
2.4 Evaluation	6
SECTION 3 - VISUAL INSPECTION	
3.1 Findings	7
SECTION 4 - OPERATIONAL FEATURES	
4.1 Procedures	9
4.2 Maintenance of the Dam	9
4.3 Maintenance of Operating Facilities	9
4.4 Warning System in Effect	9
4.5 Evaluation of Operational Adequacy	9
SECTION 5 - HYDRAULICS AND HYDROLOGY	
5.1 Evaluation of Features	10
SECTION 6 - STRUCTURAL STABILITY	
6.1 Evaluation of Structural Stability	11
SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND PROPOSED REMEDIAL MEASURES	
7.1 Dam Assessment	12
7.2 Recommendations and Proposed Remedial Measures	12

TABLE OF CONTENTS
(Continued)

APPENDIX A -	CHECKLIST, ENGINEERING DATA, DESIGN
	CONSTRUCTION, OPERATION, PHASE I
APPENDIX B -	CHECKLIST, VISUAL INSPECTION, PHASE I
APPENDIX C -	HYDROLOGIC & HYDRAULIC DATA
APPENDIX D -	PHOTOGRAPHS
APPENDIX E -	DRAWINGS
APPENDIX F -	SITE GEOLOGY

PHASE I REPORT
NATIONAL DAM INSPECTION PROGRAM
KINTZ CREEK DAM
NDI I.D. NO. 00415
DER # 52-159

SECTION 1

PROJECT INFORMATION

1.1 General

- a. Authority. The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.
- b. Purpose. The purpose of this inspection is to evaluate the structural and hydraulic conditions at Kintz Creek Dam, and to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project (Supplemented by information obtained from the Pennsylvania Department of Environmental Resources (DER), Division of Dam Safety, Harrisburg, Pennsylvania, and the Soil Conservation Service (SCS), State Office, Harrisburg, Pennsylvania).

- ABSTRACT
- a. Dam and Appurtenances. Kintz Creek Dam is a zoned earth embankment, approximately 1,180 feet in length with a maximum height of 36 feet. The top of the dam is 14 feet wide at Elevation 1626.2. The earth embankment side slopes are 3 horizontal to 1 vertical (3H:1V) upstream and 2H:1V downstream. According to the as-built plans, the embankment has a central core with 1H:1V side slopes to Elevation 1620 and a cutoff trench approximately 6 feet in depth with a 12 foot base width. The central core and cutoff trench are composed of Zone I material (silty material, classified as ML). The downstream shell to Elevation 1620 consists of Zone II material (sandy silt, classified as SP-SM). Zone III material (gravel, classified GM) forms the upstream shell and cap over the core material, and is also used as an 8-foot thick downstream filter between the Zone I and Zone II material to a minimum Elevation of 1608. A layer of Zone V material (spoil material and boulders in excess of 6 inches) covers the downstream face to Elevation 1620. A 10-foot wide berm is provided along the upstream face from Elevation 1596.8 to 1597.8. According to the as-built plans, six relief wells are spaced at 50 feet along the downstream toe. Flow from the wells enters a 4-foot wide drain trench that terminates at the Principal Spillway outlet (impact basin). The drain trench lies beneath a 15-foot wide berm with a slope of 10H:1V.

According to the as-built plans, the Principal Spillway consists of a two-stage drop inlet riser, a 36-inch diameter prestressed reinforced concrete pipe and a reinforced concrete impact basin outlet structure. The riser is 22 feet high and has inside dimensions 9 feet long and 3 feet wide. A low stage (normal pool) inlet is located on the upstream end wall at Elevation 1596.8 and consists of a 3-foot by 2-foot weir. This weir serves as a control structure for low flow which passes over the weir and through a 2.25 foot wide by 2-foot high orifice (invert Elevation 1594.0) located in the upstream end wall of the riser. High stage inlets are located on both sidewalls at Elevation 1616.0 and consist of rectangular openings. Each opening has a 9-foot long weir and a vertical dimension of 18 inches. Anti-vortex walls are incorporated into the top of the riser.

The Principal Spillway pipe rests on a concrete bedding through the base of the embankment. There are five reinforced concrete anti-seep collars at intervals of approximately 23 feet along the length of the pipe. Flow from the pipe discharges into a reinforced concrete impact basin outlet structure. Flow from the outlet structure empties into a trapezoidal channel which has a bottom width of 14 feet, 2H:1V side slopes, and is riprap lined for the initial 20 feet of its length. The centerline of the Principal Spillway is approximately 450 feet from the right abutment.

The Emergency Spillway which is located at the left abutment is a 200-foot wide trapezoidal channel with 3H:1V side slopes. The spillway was formed by excavation of the natural material at the left abutment. There is a 30-foot long level section located just downstream from the centerline of the dam. The forebay channel, about 300 feet in length, slopes upward to the level section on a 2 percent grade. The downstream channel slopes away from the level section on a 2 percent grade before blending with the natural ground about 200 feet downstream from the level section. The elevation of the level section is 1622.0.

An earth dike with 3H:1V side slopes and a 14-foot top width separates the vegetated, earth cut, spillway channel from the earth embankment for a distance of about 50 feet upstream and 150 feet downstream.

- b. Location. Kintz Creek Dam is located on Kintz Creek in Greene Township, Pike County. The dam is approximately 25 miles southeast of Scranton. The dam site is shown on the USGS Quadrangle entitled "Promised Land, Pennsylvania" at coordinates N 41° 16.9', W 75° 14.0'. A regional location plan of Kintz Creek Dam is enclosed as Plate 1, Appendix E.
- c. Size Classification. Based on the storage capacity to the top of the dam of 1,166 acre-feet, Kintz Creek Dam is classified in the "Intermediate" size category.

- d. Hazard Classification. There are approximately 5 homes along the shores of Wynooska Lake, into which Kintz Creek drains, located about a mile downstream of the dam. The topography is such that flood waters would be directed towards these homes resulting in probable loss of life and extensive property damage. Therefore, Kintz Creek Dam is considered a "High" hazard dam.
- e. Ownership. Kintz Creek Dam is owned by the Pike County Commissioners, County Courthouse, Milford, Pennsylvania, 18337.
- f. Purpose of Dam. The primary purpose of the dam is flood control.
- g. Design and Construction History. Kintz Creek Dam was designed by the engineering staff of the Soil Conservation Service (SCS) of the United States Department of Agriculture and was constructed by the Triple V Construction Company. Construction began in June of 1968 and was completed in June of 1970. There is no record of subsequent modifications to the structure.
- h. Normal Operating Procedure. Kintz Creek Dam is essentially a "Dry Dam", since the reservoir is normally at the level of the low stage weir. All hydraulic features of the Principal Spillway and Emergency Spillway are uncontrolled (no gates).

1.3 Pertinent Data.

a. Drainage Area

Square Miles	4.20
--------------	------

b. Discharge at Dam Site (cfs.)

Maximum Principal Spillway Low Stage Weir Capacity. (Reservoir surface at high stage weir level, Elev. 1616.0)	108
Maximum Principal Spillway Capacity. (Reservoir surface at Emergency Spillway crest, Elev. 1622.0)	162
Maximum combined Spillway Capacity (Reservoir surface at the top of the Dam, Elev. 1626.2)	4,500

c. Elevation (Feet above MSL)

Normal Pool	1597.0
Top of Dam	1626.2
Emergency Spillway Crest	1622.0
Principal Spillway Low Stage Inlet	1596.8
Principal Spillway High Stage Inlet	1616.0
Principal Spillway Pipe Invert (Inlet)	1594.0
Principal Spillway Pipe Invert (Outlet)	1591.5
Streambed Elevation at Dam Centerline	1590.0

d. Reservoir (Miles)

Length of Normal Pool	0.18
Length of Maximum Non-overtopping Pool	0.64

e. Storage (Acre-feet)

Normal Pool, Elev. 1596.8 (Design assumption is that 50 years of sedimentation will reduce storage at elevation 1596.8 to 0)	12
Riser High Stage Inlet, Elev. 1616.0	560
Emergency Spillway Crest (100-yr. storm), Elev. 1622.0	896
Top of Dam, Elev. 1626.2	1,166

f. Reservoir Surface Area (Acres)

Normal Pool, Elev. 1596.8	8.5
Riser High Stage Inlet, Elev. 1616.0	50.0
Emergency Spillway Crest, Elev. 1622.0	61.0
Top of Dam, Elev. 1626.2	68.5

g. Dam Data

Type	Compacted Earth Embankment
Length	1,180 feet
Height	36 feet (maximum)
Top Width	14 feet
Side Slopes	3H:1V (upstream) 2H:1V (downstream)
Zoning	Yes, refer to Section 1.2.a.
Impervious Core	A central core of relatively impervious silty material classified as ML.
Cutoff	A cutoff trench of core material.
Grout Curtain	No

h. Diversion and Regulating Tunnel

Does not apply to this site.

i. Spillways

1. A Principal Spillway which consists of a two-stage reinforced concrete drop inlet riser which outlets into a 36-inch diameter prestressed reinforced concrete pipe through the base of the embankment.

Length of Weir	18 feet (high stage) 7 feet (low stage)
Crest Elevation	Low Stage: 1596.8; High Stage: 1616.0
Gates	None

Upstream Channel
Downstream Channel

None
Trapezoidal channel approximately 150 feet long with 14-foot bottom width, and 2H:1V side slopes which are riprap lined for the initial 20 feet. Approximately 150 feet long.

2. Trapezoidal grass covered spillway with a 30-foot long level section.

Width
Crest Elevation
Gates
Upstream Channel

200 feet
1622
None

Downstream Channel

A curved channel about 300 feet in length slopes up on a 2 percent grade to the level section on a 2 percent grade. A straight channel about 200 feet in length slopes away from the level section on a 2 percent grade and terminates in the open valley downstream of the dam.

SECTION 2

ENGINEERING DATA

2.1 Design

- a. Data Available. The information available in the DER main office files in Harrisburg, Pennsylvania, for review of Kintz Creek Dam, includes the following:
 - 1) Application, Report upon the Application, and Permit to construct Kintz Creek Dam.
 - 2) Complete set of as-built plans including location and contour maps and soil boring logs.
 - 3) Yearly inspection reports.
 - 4) Construction progress photographs and reports.
 - 5) Miscellaneous correspondence, memoranda, and additional information obtained from the SCS, State Office, Harrisburg, Pennsylvania, included design calculations.
- b. Design Features. The design features are described in Section 1.2.a and shown on the Plates in Appendix E.

2.2 Construction

Based on the field investigation and the information available in the construction reports, the dam appears to have been constructed in general conformance with the design drawings.

2.3 Operation

There are no mechanical control features for Kintz Creek Dam. Refer to section 1.2.g.

2.4 Evaluation

- a. Availability. The engineering data utilized in this report were provided by DER and SCS.
- b. Adequacy. The material provided by DER and SCS is considered adequate for a Phase I investigation.
- c. Validity. There is no reason to question the validity of the data available from DER and SCS.

SECTION 3

VISUAL INSPECTION

3.1 Findings

- a. General. The field inspection of Kintz Creek Dam took place on December 5, 1978. At the time of the inspection, the reservoir surface was slightly above the crest of the low stage weir. No underwater areas were inspected. The observations and comments of the field inspection team are in the checklist which is Appendix B of this report. The appearance of the facility indicates that the dam and its appurtenances are marginally maintained.
- b. Dam. On the date of the inspection, the upstream face of the embankment appeared to be in good condition. However, on the downstream face there are numerous holes, exposed boulders, depressions, and bulges (refer to Plate D2). Variations of several feet were observed in localized areas and there was evidence of soil erosion around the boulders. A survey of the top of the dam revealed variations in ground elevations of nearly a foot. Several depressions in the top of the dam correspond to areas of animal burrowing in the downstream face. The top of the dam also has tire ruts (up to 6 inches deep) with standing water.

Standing water, 6 inches to a foot deep, is evident in a low area (75-foot by 25-foot) downstream of the embankment along the earth dike which separates the Emergency Spillway from the downstream face of the earth embankment. Two other areas (+ 2-foot by 2-foot) of standing water are located along the downstream toe of the embankment. None of this water appears to be a result of seepage through the embankment, since the reservoir level is well below the elevation of the standing water.

The top of the dam and side slopes are covered by a thick overgrowth of grass which could conceal minor surface problems.

- c. Appurtenant Structures. The visible portions of the Principal Spillway system appear to be in good condition with no signs of spalling, cracking or deterioration of the concrete.

The Emergency Spillway has an established grass cover and appears to be in good condition. There are minor undulations across its width, which should not have a significant affect on the hydraulic efficiency of the spillway.

- d. Reservoir Area. There are a number of trees standing in the upstream end of the reservoir. The slopes along the right side of the reservoir are relatively flat and wooded; those along the left side are much steeper, but show no signs of instability.
- e. Downstream Channel. The channel downstream of the Principal Spillway outlet structure is trapezoidal in shape for a distance of about 150 feet before converging into the natural stream channel. The first 20 feet of the channel downstream of the impact basin is lined with riprap.

During periods of high flow there is potential for loss of life and extensive property damage along the shores of Wynooska Lake about one mile downstream of Kintz Creek Dam. There are approximately 5 homes along the shores of Wynooska Lake.

SECTION 4

OPERATIONAL FEATURES

- 4.1 Procedures. There are no operational procedures associated with Kintz Creek Dam.
- 4.2 Maintenance of the Dam. The dam is maintained by the Pike County Commissioners. The only records of maintenance performed are reports on the completion of required maintenance following the yearly inspections. From 1972 through 1975, required maintenance consisted of grass cutting and removal of debris from the reservoir area, Principal Spillway inlet, and outlet channel. However, the 1976 and 1977 inspection reports stated that the dam was not in need of any repair or maintenance.
- 4.3 Maintenance of Operating Facilities. Removal of debris from the Principal Spillway inlet was reported to be performed periodically through 1975. There is no record of any such maintenance in the past four years.
- 4.4 Warning Systems in Effect. There is no evidence of a formal warning system or procedures to be followed during periods of heavy rainfall.
- 4.5 Evaluation of Operational Adequacy. According to inspection reports, maintenance of Kintz Creek Dam was adequate through the year 1975. Inspection reports after 1975 were very brief. Maintenance procedures were reported to be in compliance with inspection reports. However, the condition of the site during the visual inspection (December 5, 1978) revealed that current maintenance is only marginal. As stated in Section 4.1 there are no operational (mechanical) features associated with Kintz Creek Dam.

The dam is not readily accessible under all weather conditions for inspection and emergency action.

SECTION 5

HYDRAULICS AND HYDROLOGY

5.1 Evaluation of Features

- a. Design Data. The complete hydrologic and hydraulic design was obtained from SCS. Refer to Sheet 10 of Appendix C for the SCS hydrologic and hydraulics summary.

Kintz Creek Dam has a drainage area of 4.20 square miles and impounds a reservoir with a floodwater storage capacity of 896 acre-feet. The combined spillway system has a discharge capacity of 4,590 cfs.

- b. Experience Data. There are no known records of rainfall or reservoir level.
- c. Visual Observations. On the date of the inspection, there appeared to be no adverse conditions that would restrict the proper functioning of the hydraulic features of the dam. Further observations are given in Appendix B.
- d. Overtopping Potential. The Spillway Design Flood (SDF) for an Intermediate size, "High" hazard structure is the full PMF. The corresponding peak inflow and outflow rates are 9,320 cfs. and 9,290 cfs. respectively. Based on the hydrologic analyses, the combined spillway system is capable of discharging 58 percent of the PMF without overtopping of the embankment (See Appendix C for computations).
- e. Spillway Adequacy. The Kintz Creek Dam spillway system is classified as "Inadequate" since it is incapable of discharging the SDF (the full PMF).

SECTION 6

STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

- a. Visual Observations. The riser and impact basin of the Principal Spillway appear to be in good structural condition with no visible signs of concrete deterioration. The upstream face of the earth embankment shows no visible signs of instability. However, the deteriorated condition of the downstream face of the embankment (refer to Section 3.1.b. and Plate D2) is a potential source of instability. The areas of ponded water referred to in Section 3.1.b. appear to be the result of improper grading.
- b. Design and Construction Data. The design and construction data available from DER & SCS include slope stability and seepage computations. The dam was constructed as a zoned earth embankment with a downstream face consisting of "exposed rock surface covered with spoil material to assist in establishing vegetation" (Zone V). This layer is the portion of the embankment that is a potential source of instability. The Zone V material does not appear in the design drawings.
- c. Operating Records. There are no mechanical operating facilities for Kintz Creek Dam.
- d. Post Construction Changes. There is no record or visible evidence of any post construction changes.
- e. Seismic Stability. Kintz Creek Dam is located in Zone 1 on the Seismic Zone Map of Contiguous States. A dam located in Seismic Zone 1 is generally considered to be safe under any expected Zone 1 earthquake loading conditions if it is stable under static loading conditions.

SECTION 7

ASSESSMENT, RECOMMENDATIONS, AND PROPOSED REMEDIAL MEASURES

7.1 Dam Assessment

- a. Safety. The visual inspection and review of available information indicate that the Kintz Creek Dam is in fair condition.

The spillway system is capable of discharging 58 percent of the PMF without overtopping of the embankment. The SDF is the full PMF for this structure. Therefore, the spillway system is classified as "Inadequate".

The area on the downstream face of the embankment, referred to as Zone V on the as-built drawings, consists of numerous holes (2 holes were approximately 2.5 foot in depth), exposed boulders with signs of soil erosion around the boulders, bulges, and overgrown vegetation. The layer of Zone V material does not appear in the design drawings. The grass cover on the upstream face of the earth embankment and on the Emergency Spillway appears to be in good condition while the grass cover on the downstream slope of the embankment appears to be in poor condition.

Several localized depressions along the top of the dam correspond to areas of animal burrowing on the downstream face. Other areas of ponded water (refer to Section 3.1.b) appear to be the result of poor drainage due to improper grading or maintenance traffic.

- b. Adequacy of Information. A complete set of as-built plans are available from DER and extensive hydraulic, hydrologic, and structural calculations were obtained from SCS. This information is adequate for a Phase I investigation.
- c. Urgency. The remedial measures recommended in Section 7.2 should be implemented as soon as possible.
- d. Necessity for Further Investigation. In light of the condition of "Zone V" further investigation should be performed to determine if the downstream slope is safe under assumed design loading.

7.2 Recommendations and Proposed Remedial Measures

- a. Facilities. The following recommendations are made for Kintz Creek Dam:
1. Engage a professional engineer experienced in the design and construction of dams to analyze the Zone V material and perform

stability analyses. If warranted, specific corrective action should be identified and taken.

2. Low areas along the top of the dam, that appear to be the result of maintenance traffic or poor grading, should be restored to the design top of dam elevation as required.
3. The downstream area near the Emergency Spillway outlet channel and the area along the downstream toe of the earth embankment should be regraded to prevent ponding of water.

b. Operation and Maintenance Procedures.

1. The grass cover on the earth embankment should be cut on a regularly scheduled basis to permit visual inspection of the embankment.
2. A maintenance program, independent of the yearly inspection reports, should be developed and implemented.
3. A warning system should be developed. During periods of heavy rainfall, the dam should be monitored and downstream residents alerted in the event of an impending failure.

APPENDIX

A

Check List Engineering Data
Design, Construction, Operation
Phase I

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
PHASE I

NAME OF DAM KINTZ CREEK
ID # 00415

Sheet 1 of 4

ITEM

REMARKS

AS-BUILT DRAWINGS

A COMPLETE SET OF AS
BUILT PLANS WERE AVAILABLE
FROM DOK.

REGIONAL VICINITY MAP

SEE PLATE 1

CONSTRUCTION HISTORY

CONSTRUCTION PROGRESS REPORTS
AND PHOTOGRAPHS WERE OBTAINED FROM
DOK.

TYPICAL SECTIONS OF DAM

SEE PLATES

OUTLETS - PLAN

DETAILS

CONSTRAINTS

DISCHARGE RATINGS

RAINFALL/RESERVOIR RECORDS

SEE PLATES

NONE AVAILABLE

ITEM	REMARKS
------	---------

DESIGN REPORTS

NONE AVAILABLE

GEOLOGY REPORTS

A GEOLOGY REPORT WAS INCLUDED
IN THE INFORMATION OBTAINED FROM
SCS.

DESIGN COMPUTATIONS
HYDROLOGY & HYDRAULICS
DAM STABILITY
SEEPAGE STUDIES

HYDROLOGIC AND HYDRAULIC COMPUTATIONS
WERE PROVIDED BY SCS, BUT NO SEEPAGE
OR STABILITY CALCULATIONS WERE
AVAILABLE.

MATERIALS INVESTIGATIONS
BORING RECORDS
LABORATORY }
FIELD

SOIL BORING LOGS WERE INCLUDED IN
THE AS BUILT PLANS ALONG WITH
COMPACTION DATA.

POST-CONSTRUCTION SURVEYS OF DAM

SCS AS BUILT SURVEY

BORROW SOURCES

BORROW SOURCES WERE INDICATED IN
THE AS BUILT PLANS.

ITEM	REMARKS
MONITORING SYSTEMS	NONE AVAILABLE.
MODIFICATIONS	NO KNOWN MODIFICATIONS.
HIGH POOL RECORDS	NO RECORDS AVAILABLE.
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	NO SUCH REPORTS AVAILABLE.
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	NO PRIOR ACCIDENTS OR FAILURES.
MAINTENANCE OPERATION RECORDS	YEARLY INSPECTION REPORTS AND REQUIRES MAINTENANCE COMPLETION RECORDS WERE AVAILABLE FROM POER.

ITEM

REMARKS

SPILLWAY PLAN

SECTIONS

DETAILS

SEE PLATES

OPERATING EQUIPMENT
PLANS & DETAILS

NO OPERATING EQUIPMENT

MISCELLANEOUS

APPENDIX

B

Check List
Visual Inspection
Phase I

CHECK LIST
VISUAL INSPECTION
PHASE I

Sheet 1 of 11

Name Dam KINTZ CREEK DAM County PIKE State PENNA. National ID # 00415
Type of Dam EARTH Hazard Category HIGH
Date(s) Inspection DEC. 5, 1978 Weather SUNNY Temperature 45°

Pool Elevation at Time of Inspection 1597 H.S.L. Tailwater at Time of Inspection H.S.L.

Inspection Personnel:

MR. GEORGE ELIAS MR. THOMAS AHN
MR. DAVID CAMPBELL MR. DANA PIZARRO
MR. ROBERT BOWERS

MR. DAVID CAMPBELL Recorder

Remarks:

CONCRETE/MASONRY DAMS

Sheet 2 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
ANY NOTICEABLE SEEPAGE	N/A	
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	N/A	
DRAINS	N/A	
WATER PASSAGES	N/A	
FOUNDATION	N/A	

CONCRETE/MASONRY DAMS

Sheet 3 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	N/A	
STRUCTURAL CRACKING	N/A	
VERTICAL AND HORIZONTAL ALIGNMENT	N/A	
MONOLITH JOINTS	N/A	
CONSTRUCTION JOINTS	N/A	

EMBANKMENT

Sheet 4 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

SURFACE CRACKS

GAPS AND LARGE
HOLES WERE NOTED
IN DOWNSTREAM FACE.

DOWNSTREAM SURFACE
LAYER SHOULD BE REMOVED
AND REPLACED WITH
COMPACTED FILL.

UNUSUAL MOVEMENT OR
CRACKING AT OR BEYOND
THE TOE

NONE NOTED.

SLOUGHING OR EROSION OF
EMBANKMENT AND ABUTMENT
SLOPES

EROSION OF SPOIL
MATERIAL WAS EVIDENT
BETWEEN BOULDERS ON
DOWNSTREAM FACE

REPLACEMENT OF
LAYER IS
RECOMMENDED.

VERTICAL AND HORIZONTAL
ALIGNMENT OF THE CREST

CREST UNDULATIONS WERE
NOTED, WITH APPARENT
AREAS OF DEPRESSION NEAR
THE LEFT ABUTMENT.

A DETAILED SURVEY
WITH RESTORATION TO DESIGN
ELEVATION IF NECESSARY IS
RECOMMENDED.

RIPRAP FAILURES

NO RIPRAP.

EMBANKMENT

Sheet 5 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

DRAINS

NO PROBLEMS NOTED.

JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	WATER APPEARED TO BE COLLECTING NEAR THE DOWNSTREAM TOE ALONG THE EARTH DIKE WHICH SEPARATES THE EMBANKMENT FROM THE EMERGENCY SPILLWAY.	AN INVESTIGATION TO DETERMINE THE WATER SOURCE IS RECOMMENDED AND REGARDING IF REQUIRED.
---	--	---

ANY NOTICEABLE SEEPAGE	A LINE OF WATER WHICH COULD HAVE BEEN SEEPING EXTENDED ALONG THE DOWNSTREAM TOE FROM THE EMERGENCY SPILLWAY TO THE IMPACT BASIN.	CAME AS ABOVE
------------------------	---	---------------

STAFF GAGE AND RECORDER		
-------------------------	--	--

NONE.

OUTLET WORKS
(PRINCIPAL SPILLWAY)

Sheet 6 of 11

VISUAL EXAMINATION OF CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
	NONE OBSERVED.	
INTAKE STRUCTURE	THE RISER STRUCTURE APPEARED TO BE IN GOOD CONDITION.	
OUTLET STRUCTURE		THE IMPACT BASIN APPEARED TO BE IN GOOD CONDITION.
OUTLET CHANNEL		THE OUTLET CHANNEL DISCHARGES INTO THE ORIGINAL STREAM ABOUT 150 FEET DOWNSTREAM OF THE GAM. THE CHANNEL APPEARED TO BE IN GOOD CONDITION.
EMERGENCY GATE		NONE.

UNGATED SPILLWAY
(EMERGENCY SPILLWAY)

Sheet 7 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

CONCRETE WEIR

NO CONCRETE IN THE
EMERGENCY SPILLWAY -

APPROACH CHANNEL

A 300-FOOT LONG APPROACH CHANNEL
LEADS TO THE CONTROL SECTION ON A 2%
UPWARD GRADE.

DISCHARGE CHANNEL

A 200-FOOT LONG DISCHARGE CHANNEL
LEADS DOWNSTREAM OF THE DAM ON A
2% DOWNWARD GRADE.

BRIDGE AND PIERS

NONE.

GATED SPILLWAY

Sheet 8 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	N/A	
APPROACH CHANNEL	N/A	
DISCHARGE CHANNEL	N/A	
BRIDGE AND PIERS	N/A	
GATES AND OPERATION EQUIPMENT	N/A	

INSTRUMENTATION

Sheet 9 of 11

REMARKS OR RECOMMENDATIONS

VISUAL EXAMINATION

OBSERVATIONS

MONUMENTATION/SURVEYS

NONE.

OBSERVATION WELLS

NONE.

WEIRS

NONE.

PIEZOMETERS

NONE.

OTHER

NONE.

RESERVOIR

Sheet 10 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

SLOPES

THE RIGHT RESERVOIR
SLOPE IS GENTLE AND
WELL VEGETATED. THE LEFT
RESERVOIR SLOPE IS STEEP
AND ROCKY.

SEDIMENTATION

THE INTAKE STRUCTURE WAS
DESIGNED FOR 50 YEARS OF
SEDIMENTATION. THE LOW STAGE
INLET WAS ABOVE THE SEDIMENTATION
LEVEL ON THE DATE OF THE
INSPECTION.

DOWNSTREAM CHANNEL

Sheet 11 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

CONDITION
(OBSTRUCTIONS,
DEBRIS, ETC.)

THE DOWNSTREAM CHANNEL
APPEARED TO BE UNOBSTRUCTED.

SLOPES

THE AREA DOWNSTREAM OF THE
DAM IS EXTREMELY FLAT AND THE
DOWNSTREAM CHANNEL GRADE BETWEEN THE
DAM AND WYNOOSKA LAKE IS ONLY 0.5%.

APPROXIMATE NO.
OF HOMES AND
POPULATION

THERE ARE APPROXIMATELY 5
HOMES ALONG THE LEFT SHORE OF WYNOOSKA
LAKE, WHICH IS ABOUT A MILE DOWNSTREAM
OF KINTZ CREEK DAM.

APPENDIX

C

Hydrologic & Hydraulic Data

SUBJECT	SHEET	BY	DATE	JOB NO.
KINTZ CREEK DAM				

TABLE OF CONTENTS APPENDIX C

HYDROLOGIC & HYDRAULIC DATA

PMP CALCULATIONS	SHEET 1
SNYDER COEFFICIENTS	SHEET 1
SPILLWAY DISCHARGE	SHEETS 2-3
HEC-1 DAM SAFETY VERSION	SHEETS 4-9
COMPUTER OUTPUT	
SCS DESIGN SUMMARY	SHEET 10

HYDROLOGY CALCS.

DRAINAGE AREA: 4.20 SQUARE MILES

PMP CALCULATIONS (HMS REPORT 33)

AREA IS IN ZONE 1

24 HR., 200 SQ MI. RAINFALL = 22"

<u>HR.</u>	<u>%</u>	<u>RAINFALL</u>	<u>Δ RF</u>
6	111	24.4"	24.4"
12	123	27.1"	2.7"
24	133	29.3"	2.2"
48	142	31.2"	1.9"

SNYDER COEFFICIENTS

FROM INFO. PROVIDED BY COE,
FOR THE DELAWARE RIVER BASIN, ZONE 1:

$$C_p = 0.45$$

and

$$C_t = 1.23$$

$$t_p = C_t (L \cdot L_{ca})^{0.3}$$

$$L = 2.3 \text{ miles}$$

$$L_{ca} = 1.1 \text{ miles}$$

$$t_p = 1.23 (2.3 \cdot 1.1)^{0.3} = 1.62 \text{ HR.}$$

DISCHARGE AT DAMSITE VALUES (TAKEN FROM DESIGN CALCULATIONS BY SCS)

HIGH-STAGE WEIR ELEVATION (EL. 1616) → MAX. LOW STAGE FLOW = 96 CFS

EMERGENCY SPILLWAY CREST ELEVATION (EL. 1622) → MAX. HIGH STAGE FLOW = 181 CFS

TOP OF DAM ELEVATION (EL. 1626.2) → MAX. EMERGENCY SPILLWAY FLOW = 4589 CFS

SCS DESIGN CALCULATION ASSUMPTIONS DIFFER FROM AS BUILT PLANS, SO:
LOW STAGE DISCHARGE

WEIR CREST EL. = 1596.8, ORIFICE EL. = 1595

WEIR → $Q_w = CLH_w^{3/2}$ $C = 3.1, L = 7'$ $Q_w = 21.7 H_w^{3/2}$

ORIFICE CONTROL → $Q_o = CA\sqrt{2gH_o}$ $C = 0.65, A = 4.5' \times 2', \sqrt{2g} = 8.03$

$Q_o = 23.5 H_o^{3/2}$

<u>ELEV.</u>	<u>H_w</u>	<u>H_o</u>	<u>Q_w</u>	<u>Q_o</u>
1596.8	0	—	0	0
1597	.2	2	2	33
1598	1.2	3	29	41
1600	3.2	5	155 *	53
1602	5.2	7	—	62
1604	7.2	9	—	71
1606	9.2	11	—	78
1608	11.2	13	—	85
1610	13.2	15	—	91
1612	15.2	17	—	97
1614	17.2	19	—	102
1616	19.2	21	—	108

* - ORIFICE CONTROLLED ABOVE EL. 1598.4

SUBJECT	SHEET	BY	DATE	JOB NO.
	3			

HIGH STAGE DISCHARGE

WEIR CREST EL. = 1616

BAFFLE BLOCK CONTROL ELEVATION = 1596.5

$$\text{WEIR} \rightarrow Q_w = CLH_w^{3/2} \quad C = 3.1, L = 18'$$

$$Q_w = 55.8 H_w^{3/2}$$

$$\text{PIPE} \rightarrow Q_p = KA \sqrt{2gH_p} \quad K = .565 \text{ (FROM JCS)}$$

$$Q_p = 32.06 H_p^{1/2}$$

ELEV.	H_w	H_p	Q_w	$Q_w + Q_p$	Q_p
1616	0	19.5	0	108	142
1616.5	.5	20	20	129	143
1617	1	20.5	55.8	166*	145
1618	2	21.5	—	—	149
1619	3	22.5	—	—	152
1620	4	23.5	—	—	155
1621	5	24.5	—	—	159
1622	6	25.5	—	—	162

* - PIPE CONTROLS ABOVE ELEV. 1616.7

EMERGENCY SPILLWAY (FROM JCS CALCULATIONS)

ELEV.	H_{es}	Q_{es}	Q_p	Q_{TOTAL}
1622	0	0	162	162
1623.6	1.6	1009	167	1176
1624.65	2.65	2029	170	2199
1625.39	3.39	3057	172	3229
1626.04	4.04	4092	174	4266
1627.14	5.14	6183	177	6360
1628.14	6.14	8296	180	8476

.....
 FLOOD HYDROGRAPH PACKAGE (MEC-1)
 DAM SAFETY VERSION JULY 1976
 LAST MODIFICATION 25 SEP 78

SHEET 4

NATIONAL DAM INSPECTION PROGRAM									
KINTZ CREEK DAM									
PMF HYDROGRAPH									
1	A1	0	0	0	0	0	0	0	0
2	A2	15	0	0	0	0	0	0	0
3	A3	0	0	0	0	0	0	0	0
4	B	0	0	0	0	0	0	0	0
5	C	0	0	0	0	0	0	0	0
6	D	0	0	0	0	0	0	0	0
7	E	0	0	0	0	0	0	0	0
8	F	0	0	0	0	0	0	0	0
9	G	0	0	0	0	0	0	0	0
10	H	0	0	0	0	0	0	0	0
11	I	0	0	0	0	0	0	0	0
12	J	0	0	0	0	0	0	0	0
13	K	0	0	0	0	0	0	0	0
14	L	0	0	0	0	0	0	0	0
15	M	0	0	0	0	0	0	0	0
16	N	0	0	0	0	0	0	0	0
17	O	0	0	0	0	0	0	0	0
18	P	0	0	0	0	0	0	0	0
19	Q	0	0	0	0	0	0	0	0
20	R	0	0	0	0	0	0	0	0
21	S	0	0	0	0	0	0	0	0
22	T	0	0	0	0	0	0	0	0
23	U	0	0	0	0	0	0	0	0
24	V	0	0	0	0	0	0	0	0
25	W	0	0	0	0	0	0	0	0
26	X	0	0	0	0	0	0	0	0
27	Y	0	0	0	0	0	0	0	0

RUNOFF TO RESERVOIR

1	1598	1600	1602	1606	1610	1614	1616	1616.5
2	1620	1622	1623.6	1624.65	1625.39	1626.04	1627.14	1628.14
3	1629	1631	1632.2	1633.2	1634.2	1635.2	1636.2	1637.2
4	1638	1640	1641.2	1642.2	1643.2	1644.2	1645.2	1646.2
5	1647	1649	1650.2	1651.2	1652.2	1653.2	1654.2	1655.2
6	1656	1658	1659.2	1660.2	1661.2	1662.2	1663.2	1664.2
7	1665	1667	1668.2	1669.2	1670.2	1671.2	1672.2	1673.2
8	1674	1676	1677.2	1678.2	1679.2	1680.2	1681.2	1682.2
9	1683	1685	1686.2	1687.2	1688.2	1689.2	1690.2	1691.2
10	1692	1694	1695.2	1696.2	1697.2	1698.2	1699.2	1700.2
11	1701	1703	1704.2	1705.2	1706.2	1707.2	1708.2	1709.2
12	1710	1712	1713.2	1714.2	1715.2	1716.2	1717.2	1718.2
13	1719	1721	1722.2	1723.2	1724.2	1725.2	1726.2	1727.2
14	1728	1730	1731.2	1732.2	1733.2	1734.2	1735.2	1736.2
15	1737	1739	1740.2	1741.2	1742.2	1743.2	1744.2	1745.2
16	1746	1748	1749.2	1750.2	1751.2	1752.2	1753.2	1754.2
17	1755	1757	1758.2	1759.2	1760.2	1761.2	1762.2	1763.2
18	1764	1766	1767.2	1768.2	1769.2	1770.2	1771.2	1772.2
19	1773	1775	1776.2	1777.2	1778.2	1779.2	1780.2	1781.2
20	1782	1784	1785.2	1786.2	1787.2	1788.2	1789.2	1790.2
21	1791	1793	1794.2	1795.2	1796.2	1797.2	1798.2	1799.2
22	1800	1802	1803.2	1804.2	1805.2	1806.2	1807.2	1808.2
23	1809	1811	1812.2	1813.2	1814.2	1815.2	1816.2	1817.2
24	1818	1820	1821.2	1822.2	1823.2	1824.2	1825.2	1826.2
25	1827	1829	1830.2	1831.2	1832.2	1833.2	1834.2	1835.2
26	1836	1838	1839.2	1840.2	1841.2	1842.2	1843.2	1844.2
27	1845	1847	1848.2	1849.2	1850.2	1851.2	1852.2	1853.2

ROUTING THROUGH RESERVOIR

1	1598	1600	1602	1606	1610	1614	1616	1616.5
2	1620	1622	1623.6	1624.65	1625.39	1626.04	1627.14	1628.14
3	1629	1631	1632.2	1633.2	1634.2	1635.2	1636.2	1637.2
4	1638	1640	1641.2	1642.2	1643.2	1644.2	1645.2	1646.2
5	1647	1649	1650.2	1651.2	1652.2	1653.2	1654.2	1655.2
6	1656	1658	1659.2	1660.2	1661.2	1662.2	1663.2	1664.2
7	1665	1667	1668.2	1669.2	1670.2	1671.2	1672.2	1673.2
8	1674	1676	1677.2	1678.2	1679.2	1680.2	1681.2	1682.2
9	1683	1685	1686.2	1687.2	1688.2	1689.2	1690.2	1691.2
10	1692	1694	1695.2	1696.2	1697.2	1698.2	1699.2	1700.2
11	1701	1703	1704.2	1705.2	1706.2	1707.2	1708.2	1709.2
12	1710	1712	1713.2	1714.2	1715.2	1716.2	1717.2	1718.2
13	1719	1721	1722.2	1723.2	1724.2	1725.2	1726.2	1727.2
14	1728	1730	1731.2	1732.2	1733.2	1734.2	1735.2	1736.2
15	1737	1739	1740.2	1741.2	1742.2	1743.2	1744.2	1745.2
16	1746	1748	1749.2	1750.2	1751.2	1752.2	1753.2	1754.2
17	1755	1757	1758.2	1759.2	1760.2	1761.2	1762.2	1763.2
18	1764	1766	1767.2	1768.2	1769.2	1770.2	1771.2	1772.2
19	1773	1775	1776.2	1777.2	1778.2	1779.2	1780.2	1781.2
20	1782	1784	1785.2	1786.2	1787.2	1788.2	1789.2	1790.2
21	1791	1793	1794.2	1795.2	1796.2	1797.2	1798.2	1799.2
22	1800	1802	1803.2	1804.2	1805.2	1806.2	1807.2	1808.2
23	1809	1811	1812.2	1813.2	1814.2	1815.2	1816.2	1817.2
24	1818	1820	1821.2	1822.2	1823.2	1824.2	1825.2	1826.2
25	1827	1829	1830.2	1831.2	1832.2	1833.2	1834.2	1835.2
26	1836	1838	1839.2	1840.2	1841.2	1842.2	1843.2	1844.2
27	1845	1847	1848.2	1849.2	1850.2	1851.2	1852.2	1853.2

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 25 SEP 78

RUN DATE 04/09/79.
 TIME 09.57.39.

NATIONAL DAM INSPECTION PROGRAM
 KINTZ CREEK DAM
 PMF HYDROGRAPH

JOB SPECIFICATION									
NO	NHR	NMIN	IDAY	IMR	IMIN	METRC	IPLI	IPRT	NSTAM
300	0	15	0	0	0	0	0	0	0
			JOPER	NAT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOS= .20 .30 .40 .50 .60 .70 .80 .90 1.00
 NPLAN= 1 NRTIO= 9 LRTIO= 1

***** SUB-AREA RUNOFF COMPUTATION *****

SUB-AREA RUNOFF COMPUTATION

RUNOFF TO RESERVOIR

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRI	INAME	ISTAGE	IAUTO
21	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

IMYDG	IUMG	TAREA	SNAP	TRSDA	TMSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	4.20	0.00	4.20	0.00	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	22.00	111.00	123.00	133.00	0.00	0.00	0.00

TRSPC COMPUTED BY THE PROGRAM IS .800

LOSS DATA

LKOPT	STKR	DLTKH	RTIOL	ERAIN	STPKS	RTIOK	STRTL	CNSTL	ALSHX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA
 TP= 1.62 CP= .45 NTA= 0

RECESSION DATA

STRTQ= -1.50 ORCSN= -.05 RTIOR= 2.00

UNIT HYDROGRAPH 59 END-OF-PERIOD ORDINATES, LAG= 1.62 HOURS, CP= .45 VOL= 1.00

39.	147.	299.	469.	622.	723.	756.	717.	773.	651.	591.
536.	487.	442.	401.	364.	331.	300.	273.	248.	225.	200.
185.	168.	153.	139.	126.	114.	104.	94.	86.	86.	86.
78.	70.	64.	58.	53.	48.	43.	39.	36.	33.	33.
30.	27.	24.	22.	20.	18.	17.	15.	14.	12.	12.

SHEET 7

PEAK OUTFLOW IS 8361. AT TIME 17.50 HOURS

PEAK OUTFLOW IS 9291. AT TIME 17.50 HOURS

.....

.....

.....

.....

.....

SHEET 8

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS								
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8	RATIO 9
				.20	.30	.40	.50	.60	.70	.80	.90	1.00
HYDROGRAPH AT	A1	4.20 (10.88)	1	1864.	2797.	3729.	4661.	5593.	6525.	7457.	8390.	9322.
			(52.791	79.191	105.581	131.981	158.381	184.771	211.171	237.571	263.961
ROUTED TO	A2	4.20 (10.88)	1	157.	1139.	2476.	3736.	4983.	6234.	7371.	8361.	9291.
			(4.431	32.261	70.121	105.791	141.111	176.531	208.731	236.751	263.101

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1596.80 0. 0.	SPILLWAY CREST 1596.80 0. 0.	TOP OF DAM 1626.20 1166. 4571.	RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
					.20	1620.43	0.00	606.	157.	0.00	25.75	0.00
					.30	1623.54	0.00	995.	1139.	0.00	21.00	0.00
					.40	1624.85	0.00	1079.	2476.	0.00	19.50	0.00
					.50	1625.71	0.00	1134.	3736.	0.00	19.00	0.00
					.60	1626.33	.13	1174.	4923.	1.00	18.50	0.00
					.70	1626.60	.40	1191.	6234.	2.25	18.00	0.00
					.80	1626.79	.59	1204.	7371.	3.00	17.50	0.00
					.90	1626.95	.75	1214.	8361.	4.00	17.50	0.00
					1.00	1627.08	.88	1223.	9291.	4.00	17.50	0.00

PA 439

6/30/67
DAS

U. S. DEPARTMENT OF AGRICULTURE - SOIL CONSERVATION SERVICE

Element of Structure	Determining Factor	Elevation	Surface Area Acres	Storage		Inflow		Peak Outflow c.f.s.
				Acres-Feet	Inches	Volume Inches	Rate c.f.s.	
INVERT OF ORIFICE	50 YEAR SEDIMENT ACCUMULATION	1596.8	8.5	0	0	—	—	—
CREST OF RISER	12 Hr. DELAY FOR 100 Yr. 6 Hour STORM MOISTURE CONDITION II	1616.0	50.0	LL 560	2.5	—	—	96
CREST OF EMERGENCY SPILLWAY	4" STORAGE GREATER THAN 100 YEAR FREQUENCY STORM	1622.0	61.0	LL 896	4.0	—	—	181
DESIGN HIGH WATER	BELOW EMER. SPW. CREST - USING I. x VALUE FROM 55-1020 SH 2 of 5 and ALG. 11. No DATA COMPUTED	—	—	—	—	—	—	—
Top of Dam	PA. DEPARTMENT OF FOREST & WATERS "C" CURVE	1626.2	68.5	LL 1166	5.2	—	—	4589 ^{L2}

** REFER TO HYDROLOGIC CRITERIA IN NATIONAL MEMORANDUM SCS-27

LL DOES NOT INCLUDE 12.5 AL-FX SEDIMENT STORAGE

L2 TOTAL INCLUDES PIPE FLOW


HYDRAULICS & HYDROLOGY DESIGN SUMMARY

SHEET 10


APPENDIX

D

Photographs



*UPSTREAM FACE OF THE DAM
WITH THE RISER IN THE BACKGROUND*



*RISER SHOWING DETAILS OF BOTH
THE HIGH STAGE AND LOW STAGE INLETS*



***DIFFERENTIAL SETTLEMENT IN THE
DOWNSTREAM FACE OF THE DAM***



***LARGE HOLES AND BOULDERS IN THE
DOWNSTREAM FACE OF THE DAM***



*DEPRESSED AREA ALONG THE UPSTREAM SIDE
OF THE IMPACT BASIN*



*PRINCIPAL SPILLWAY IMPACT BASIN OUTLET
AND OUTLET CHANNEL*

APPENDIX


E

Drawings

SUBJECT	SHEET	BY	DATE	JOB NO
Lantz Creek Dam				

APPENDIX E Table of Contents



Regional Vicinity Map	Plate 1
Plan of Structural Works	" 2
Fill Placement	" 3
Principal Spillway	" 4
Cut-Off Trench Details	" 5
General Plan Drawing (Showing Problem Areas)	" 6
Top of Dam Profile	" 7



EMERGENCY SPILLWAY & CURVE DATA

Station	Deflection Δ	Chord
PC=1+99.8	0°-00'	—
2+29.8	4°-18'	30.00
2+59.8	8°-36'	30.00
2+89.8	12°-54'	30.00
3+19.8	17°-12'	30.00
3+49.8	21°-30'	30.00
3+79.8	25°-48'	30.00
4+09.8	30°-06'	30.00
4+39.8	34°-24'	30.00
4+69.8	38°-42'	30.00
PT=5+00	43°-00'	30.00



$I = 86^{\circ}-00'$
 $R = 200'$
 $T = 186.50'$
 $L_c = 300.20'$
 $C = 272.80'$
 $M = 53.73'$
 $E = 73.47'$
 $PC = 1+99.8$
 $PT = 5+00$




TYPICAL PLAN OF

CONSTRUCTION


- 1 - For logs of drill hole
- 2 - Δ Dam = Δ Cutoff
- 3 - Riprap bedding shown on sheet
- 4 - Fill gullies with diversion.



Constructed As Shown w.w



Constructed As Shown w.w



DIVERSION DETAILS
Not to Scale

CONSTRUCTION NOTES:

- 1- For logs of drill holes & test pits see sheets 10 thru 21.
- 2- ∇ Dam = ∇ Cutoff Trench
- 3- Riprap bedding shall meet fine drain fill gradation shown on sheet 2.
- 4- Fill gullies with approved spoil before building diversion.

2

PLATE 2

AS BUILT PLANS


As Built Plans 9-70 w.w

GREENE-DREHER WATERSHED
FLOODWATER RETARDING DAM, PA-439
PIKE COUNTY, PENNSYLVANIA

PLAN OF STRUCTURAL WORKS


U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed by D. Shokley	Date Aug '67	Reviewed by T. J. Hays
Drawn by T. J. Hays	Scale 8-47	Check by T. J. Hays
Project Floodwater Retarding Dam	Sheet No. 3	PA-439-P




TYPICAL SECTION OF DAM

TYPICAL SECTION OF DIKE



TYPICAL SECTION OF DAM (FROM DAM STA. 1+40 TO STA. 2+00 AND STA. 11+80 TO STA. 12+90 (APPROX))

ZONE
I
II
III
V



TYPICAL SECTION OF DAM (FROM DAM STA 2+00 TO STA 11+80 (APPROX.))

ZONE	MATERIAL	MAX. ROCK SIZE	MAX. LIFT	REQ'D WATER CONTENT (%)	COMPACTION	
					Class	Definition
I	Material as represented by TP 106.1, depth 14.2' classified as ML; by TP 101.1, depth 1-17.5' classified as "CL"	6"	9"	Optimum + 2%	A	95% max. density by ASTM 618 Method "A"
II	Material as represented by TP 213.0, depth 1-8'; classified as SP-SM	6"	9"	Optimum ± 2%	A	95% max. density by ASTM 618 Method "A"
III	Material as represented by TP 207.1, depth 1-9.5'; classified as GH	6"	9"	Optimum ± 2%	A	95% max. density by ASTM 618 Method "A"
V	Gravel-Stones-Boulders in excess of 6" removed from Emergency Embankment	24"	36"	See Spec 5	T	See Spec 5

1. Maximum permissible lift thickness before compaction.
2. Water content of fill matrix at time of compaction.
3. For typical compaction curves see sht. 22

AS BUILT PLANS

0 2 5 10 20
SCALE - FEET

PLATE 3



GREENE-DREHER WATERSHED
FLOODWATER RETAINING DAM, PA-439
PIKE COUNTY, PENNSYLVANIA

FILL PLACEMENT

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Small 1 1/2" x 1 1/2" 8-57
C CRISE 8-57

PA-439-P





AS BUILT
36" ID PIPE JOINT DATA

JOINT	Dist. FROM RISER WALL	INVERT EL.
J-1	0.33	1594.00
J-2	8.33	1594.00
J-3	16.33	1594.00
J-4	24.33	1593.97
J-5	32.33	1593.97
J-6	40.33	1593.97
J-7	48.33	1593.97
J-8	56.33	1593.97
J-9	64.33	1593.97
J-10	72.33	1593.97
J-11	80.33	1593.97
J-12	88.33	1593.97
J-13	96.33	1593.97
J-14	104.33	1593.97
J-15	112.33	1593.97
J-16	120.33	1593.97
J-17	128.33	1593.97
J-18	136.33	1593.97
J-19	144.33	1593.97
J-20	152.33	1593.97
OUTLET	160.33	1593.97

AS BUILT
COLLAR DATA FOR 36" ID. PIPE

COLLAR	DIST. FROM RISER WALL	INVERT EL.
1	22	1593.99
2	44	1593.99
3	67	1593.99
4	90	1593.99
5	114	1593.99

36" ID. Reinf.
160' - Straight
- Spigot
Pressure
Load
Min 3
0.0
0.0
160.33' - Tot



36" I.D. Reinforced concrete pressure pipe spillway conduit

160' - Straight sections

- Spigot ring wall fitting (For 12" wall)
- Pressure head = 29'
- Load = 27,919 lbs per lin ft, based on O.D. of 36.67'
- Min 3 edge bearing strength for:
- 0.01" Crack non-prestressed pipe = 13,551 lbs per lin ft
- 0.001" Crack prestressed pipe = 10,189 lbs per lin ft

160.33' - Total length

AS BUILT PLANS

GREENE-DREHER WATERSHED

FLOODWATER RETARDING DAM, PA-439

PIKE COUNTY, PENNSYLVANIA


PRINCIPAL SPILLWAY

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Underway 8-57
C. CRISE 9-67

PLATE 4


PA-439-P




8+00 6+00 4+00 2+00 0+00

CONSTRUCTION NOTES

1. For logs of test holes see shs. 18 thru 21



Cut-off Trench From
Field Bk #1 Page 36+38



TYPICAL SECTION OF CUT-OFF TRENCH

AS BUILT PLANS

As Built Plans 7-69 W.W.

GREENE-DREHER WATERSHED
FLOODWATER RETARDING DAM, PA-439
PIKE COUNTY, PENNSYLVANIA


CUT-OFF TRENCH DETAILS

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed by <i>Donald R. Shaddy</i>	Date <i>7-67</i>
Drawn by <i>C. CRIDE</i>	Date <i>8-67</i>
Checked by <i>J. J. J. J. J.</i>	Date <i>9-67</i>
Project No. <i>PA-439-P</i>	Sheet No. <i>5</i>

PLATE 5

CUT-OFF TRENCH



SCALE: 1" = 200'

PLATE 6
GENERAL PLAN
DRAWING

SUBJECT

KINTZ CREEK DAM

SHEET


BY

DATE

JOB NO

PLATE 7

TOP OF DAM PROFILE



HOR. SCALE : 1" = 160'
VERT. SCALE : 1" = 2'

ELEV. 1622.0 (ASSUMED)

EMERGENCY SPILLWAY

APPENDIX

F

Site Geology

SITE GEOLOGY

KINTZ CREEK DAM

Kintz Creek Dam is situated in Pike County and within the limits of the Eastern Glaciated section of the Appalachian Plateau physiographic province. Thick deposits of glacially derived rock debris cover the nearly horizontally bedded, red, gray and green shale and sandstone units of the Devonian Catskill group continental sediments. Modification of the glacial deposits during the Pleistocene epoch by natural damming downstream of the Kintz Creek Dam site provided granular kame and fine grained, varved lacustrine deposits in the present dam and lake area. These features, where encountered in the dam foundation, were suitably addressed by the dam designers.

No known faults or major structural defects are known to exist in the bedrock units in the vicinity of the lake and dam.




PLATE 1
REGIONAL
GEOLOGY MAP
SCALE 1:24000